

BRUHATH BANGALORE MAHANAGARA PALIKE

Dasarahalli Zone

NAME OF WORK: Repairs & Maintanance of Borewells at Sidedahalli Village Limit in Bagalagunte Ward No 14

Description Of Item	Unit	No	L	B	D	Est. Cost		
						RS	30.00	Lakhs
						Qty	Rate	Amount
physical survey geophysical investigation of site for sinking well for supplying drinking water to the habitation either through the hand pumps, MWS or PWSS by vertical electrical sounding by adopting venner or schlumbergers's method including reconnaissance suevey of geological formation Geophysical investigation of existing ground Water in the vicinity. its quality , quantity & acceptability of the users indicating the location of the site recommended depth of casing pipe required to seal the top consolidated formation including an extra depth 1.0 metre in consolidated formation for aquire proposed to be tapped propable and other information required including transportation of instrument and accessories to work site, engating technical personal and labour etc., PRE- Bangalore Circle-2014-15 Page No-47 & 48 ,								
	Each	1				1.00	1938.46	1938.00
sinking of Borewell of 165 mm clear using fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over burden upto 22 m fixing of casing pipes, collars and cap with necessary cutting and threading including transporation of rig and supporting vehicles, screws charges and cost of consumable including yield testing at the final depth with a minimum working of compressor for one hour all as specified., PRE- Bangalore Circle-2014-15 Page No-46. Item No-9.1.1 to 9.1.7								
							Per/Rmtr	
00 to 50.00 mtrs	Rmtr	1	50.00			50.00	315.18	15759.00
50.00 to 100.00 mtr		1	50.00			50.00	412.60	20630.00
100.00 to 150.00 mtr		1	50.00			50.00	458.35	22918.00
150.00 to 200.00 mtr		1	50.00			50.00	484.10	24205.00
200.00 to 250.00 mtr		1	50.00			50.00	560.32	28016.00
250.00 to 300.00 mtr		1	50.00			50.00	600.49	30025.00
300.00 to 350.00 mtr		1	50.00			50.00	640.60	32030.00
350.00 to 365 Mtr		1	15.00			15.00	677.74	10166.00
supply of ISI Mark 175mm Nominal bore ,plain end steel Casing pipe- grade of steel Fee 410 of wall thickness 5.4 mm thick confirming to IS 1387/1933 and manufactured by basic open hearth electric or basic oxygen process in random lenth of 5 to 7mtrs. Both ends threaded Confirming to IS 554/1985, One end fixed with a socket Confirming to IS 4270:2001 and the other end with Screwed pipes . All pipes shall be reasonably free from defectes. The tube shall be reasonably straight should be with ISI marking, weighing 5.10kg/mtr. (Inclusive of all taxes) (PRED,2012-13 Page No.iii, item No-84)								

2

		1	30			30.00	1325.00	39750.
Laying and Fixing 250mm dia PVC pipe and as per Specification Direction (BWSSB SR 13-14, P.No.53, IT.No01 of SI No.11)								
	Each	1	18			18.00	1133.00	20394
Laying 175 mm dia MS Collar (RDED SR page ii, item86)								
	Each	1	13			13.00		
						13.00	150.00	1950.
Laying 175 mm dia MS Cap(as per RDED SR page ii, item-85)								
	Each	1	1			1.00	100.00	100.0
Supply and delivery at site brand new submersible pumpset suitable for borewell of 165mm dia and having the declared duty conditions as stated below and satisfying performance Characteristics for pump motor as declared by the bureau of indian stand. the pumpset should conform to IS : 8034-1989 (With all its latest amendments) Should bear ISI Certification mark IS : 8034-1989 Submersible pumpset 20HP 40 stage Texmo/Taro or equivalents Brands (KPWD SR 2018-19 Page No: XLII Item No.56)								
	No	1	1			1.00	85197.50	85198
Basic Rate	80375.00							
Area Weightage 6%	4822.50							
Total	85197.50							
Laying and fixing of 50mm G.I pipe 'B' class heavy duty for connection of submersible pumpset galvanised tube 50mm supply and delivery of cause heavy duty as per IS/239/1990 (P No.XLVII, SL.No SR 2018-19)								
	Mtrs	1	300			300.00	439.90	13197
Basic Rate	415.00							
Area Weightage 6%	24.90							
Total	439.90							
Supplying and Drawing 3 core Flat PVC Sheathed Submersible Pump Cable Manufactured with Electrolytic Grade Copper with Flexible Copper conductor to table 3 class 5 of IS 8130-1984 and Virgin PVC Insulation and Sheathed Suitable for working Voltage Upto 1100 Volts BWSSB SR 2014-15, P- 535, I. 30Page no:12 sl no: 2.10.4								
	Mtrs	1	550.00			550.00		
						550.00	164.29	903

2

Supplying and delivery at site brand new star / Essen / Lotus / Sun shines / Adharsh / GK Controls best indigenous make combined energy meter cum control panel board unit of size 1200x600x350mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3ph, 50 hz, 380/440 volts, AC supply with spring loaded latch, locking device with a key ribs should be provided inside the door canopy apron and louvers ventilators shall be provided the combined energy meter cum control panel board unit suitable for operation on 3ph, 50 hz, 380/440 volts AC supply shall be consists etc., complete the panel board shall be consist etc., complete the panel board shall be fabricated on single unit in the above componenets panel board for suitable pumpset with star delta staretr out door type 10hp to 15 hp PRED ISSUE RATE								
0	Nos	1	1			1.00	14800.00	14800.00
Fabricating Supplying and mounting MS Box of 16 SWG suitable for floor/ wall mounting fully weather proof with provision for better hear description, 9Providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamp with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 Sq cm (P.No.530, I.No.39, BWSSB SR 2013-14)								
	Sqm Cm	1	1100.00	20.00		22000.00	0.35	7696.00
	Basic Rate	0.33						
	Area Weightage 6%	0.02						
	Total	0.35						
Providing & Fixing of Clamps set and Borewell cap to the pump 9MR)								
	No's	1				1.00	1908.00	1908.00
	Basic Rate	1800.00						
	Area Weightage 6%	108.00						
	Total	1908.00						
Supplying and fixing 50mm Non Return Vavle of vertical type of approved make including cost of all materials labour HOM of equipment with all leads Complete as per Specifcation PWD SR 2018-19, P.No-XLVII, Sl No.16								
0		1	1			1.00	1908.00	1908.00
	Basic Rate	1800.00						
	Area Weightage 6%	108.00						
	Total	1908.00						
Supplying and fixing 50mm GM Gate Vavle PWD SR 2018-19, P.No-XLVII, Sl No.15								

2

0		Nos	1	1			1.00	1908.00	1908.00
	Basic Rate	1800.00							
	Area Weightage 6%	108.00							
	Total	1908.00							
	Providing & Fixing of 50mm GI Short bend to motor (PWD SR 2018-19, P.No.XXXIX, GI Pipe Fittings, ISI Standard Table								
		No	1	1			1.00	232.14	232.00
	Basic Rate	219.00							
	Area Weightage 6%	13.14							
	Total	232.14							
	Supplying and fixing 50mm GI Union PWD SR 2015-16, P.No.XXXVII,								
		Nos	1	1			1.00	237.12	237.00
	Basic Rate	223.70							
	Area Weightage 6%	13.42							
	Total	237.12							
	Supplying and fixing 50mm GI Elbow PWD SR 2015-16, P-XXXVII								
		Nos	1	1			1.00	111.80	112.00
	Labour charges for laying 1.1 KV class UG cable when supplied by agencies in existing trenches GI pipe / stoneware pipe/ on pole as required, P-427, I-11 (a), BWSSB SR 2012-13.								
		per Length	1	50			50.00	90.64	4532.00
	Basic Rate	88.00							
	Area Weightage 3%	2.64							
	Total	90.64							
9	Erection of combined panel board and meter unit with necessary materials and labour including providing cement concrete foundation bed cont door type etc., complete PRED ISSUE RATE								
		No	1	1			1.00	475.00	475.00
0	Supplying and fixing miniature Circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required P-526, I-13 (P, a), BWSSB SR 2013-14.								
		No's	1	1			1.00	906.40	906.00
	Basic Rate	880.00							
	Area Weightage 3%	26.40							
	Total	906.40							
1	Supplying and laying of L.T.U.G Cable having aluminium conductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 K V class 4 crore 16 sqmm cable 9Confirming to IS 1554) P.No.553, IT.No 10(d) BWSSB SR 2013-14								

2

	Mtr	1	45.00			45.00	169.95	7648.00
Basic Rate	165.00							
Area Weightage 3%	4.95							
Total	169.95							
Digging of trench of 0.6m deep x 0.5m wide refilling the trench to the required level and consolidating etc., complete P-554, I-12 (b), BWSSB SR2013-14.								
	Mtrs	1	45			45.00	56.65	2549.00
Basic Rate	55.00							
Area Weightage 3%	1.65							
Total	56.65							
Supplying and fixing class A GI pipe on pole/Wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class 40mm 9P.No.555, IT No.15 (b) BWSSB SR 2013-14.								
	Mtrs	1	3			3.00	249.26	748.00
Basic Rate	242.00							
Area Weightage 3%	7.26							
Total	249.26							
Supplying, fixing, wiring earth electrode for grounding conduits, LC cutouts and other equipments on the meter board using 40mm dia 2.90mm thick GI pipe 2.50m long buried in a pit. The pit should be filled with equal proportion of salt and charcoal 150mm around the pipe to complete depth. the connection from the pipe to the conduct etc., is to be established through GI wire of size as per ISI specifications 7.3.3 IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 12mm dia P-552, I-7. BWSSB SR 2013-14.								
	No's	1	1			1.00	1699.50	1700.00
Basic Rate	1650.00							
Area Weightage 3%	49.50							
Total	1699.50							
Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmm UG cable filled with necessary bitumen / insulating compound complete with terminalas, clamps, bolts, nuts, washers etc., P-555, I No-16(b). BWSSB SR 2013-14								
	No's	1				1.00	271.92	272.00
Basic Rate	264.00							
Area Weightage 3%	7.92							
Total	271.92							
Supplying Shunt capacitor's conforming to IS 2834, 3phase 400/440 volts grade for power factor improvement of rotating machinery capacitor in KVAR rating No's (MR)								
	No's	1				1.00	1350.00	1350.00

(Signature)

Providing & Fixing Gun Metal Gate wheel valve confirming to IS Specification of approved make as per direction including all lead and lift etc., complete 50mm dia 9P.No.94, It.No.13.796, PWD SR 18-19								
	No's	1	3			3.00	778.04	2334.00
Basic Rate	734.00							
Area Weightage 6%	44.04							
Total	778.04							
Supplying and fixing of polished wood board made up not less than 15mm thick plank in both side with plank made out on not more than 2 piecess and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20x20x2.5 inches (P.No.521, I.No.2(f), BWSSB SR 2013-14								
	No's	1				1.00	311.58	312.00
Basic Rate	302.50							
Area Weightage 3%	9.08							
Total	311.58							
Earthwork excavation for foundation of buildings water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. Noll KBS 2.1.C/2.9.4/2.18/2.19 (Pg. No-06, I.No-2.4)PWD - SR 2018-19)								
Borewell Surrounding Connection	Cum	1	135.00	0.60	0.75	60.75		
						60.75	475.94	28913.00
Basic Rate	449.00							
Add Area Weightage 6%	26.94							
Total	475.94							
Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.)pg no 99,it no.13.87.8.PWD - SR 2018-19)								
Borewell Surrounding Connection	Rmt	1	135.00			135.00		
						135.00	1908.00	257580.00
Basic Rate	1800.00							
Add Area Weightage 6%	108.00							
Total	1908.00							

22

KSRB-2-4: Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m including cost of all labour complete as specifications.. allow 60% of rate considered under item KSRB 2.3 Page No. 7/ Item No. 2.11/PWD SR 2018-19)

Borewell Surrounding Connection		1	135	0.60	0.75	60.75		
Basic Rate	121.00					60.75		
Add Area Weightage 6%	7.26					60.75	128.26	7792.00
Total	128.26							
KPTCL Deposit Charge								
	Each	1				1.00	12000.00	12000.00
Borewell registration charge per Rs 1000 each for BWSSB								
	Each	1				1.00	1000.00	1000.00
Supply and delivery at site brand new Texmo / Innoval / Lubi / Sabar / Atalanta / Calamal / waterman / Radha make suitable vertical installation in 150mm dia. Borewells comprising of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for operation of 3Ph., 50Hz. 380/44 volts AC supply fitted with required accessories such as suction. casing, suction strainers, sand guard Non return valve etc., complete the pump and motor shall form an integral unit with all the required fittings 20HP 10 stage Kirloskar, Atlanta, Suguna, CRI & other equipment pump PWD SR 18-19 Page No XLII, Item. No 54								
	No	2				2.00		
						2.00	74287.00	148574.00
Supply and delivery at site brand new Texmo / Innoval / Lubi / Sabar / Atalanta / Calamal / waterman / Radha make suitable vertical installation in 150mm dia. Borewells comprising of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for operation of 3Ph., 50Hz. 380/44 volts AC supply fitted with required accessories such as suction. casing, suction strainers, sand guard Non return valve etc., complete the pump and motor shall form an integral unit with all the required fittings 20HP 5 stage Kirloskar, Atlanta, Suguna, CRI & other equipment pump PWD SR 18-197 Page No XLII, Item. No 58								
	No	1				1.00		
						1.00	78833.00	78833.00
Supplying and Drawing 3 core Flat PVC Shalted Submersible Pump Cable Manufactured with Electrolytic Grade Copper with Flexible Copper conductor to table 3 class 5 of IS 8130-1984 and Virgin PVC Insulation and Sheated Suitable for working Voltage Upto 1100 Volts BWSSB SR 2012-13, P- 535, I. 30								
	Mtrs	1	2500.00			2500.00		
						2500.00	159.50	398750.00

24

Supplying and fixing 50mm Non Return Vavle of vertical type of approved make including cost of all materials labour HOM of equipment with all leads Complete as per Specifcation PWD SR 2018-19, P.No-XLVII, SI No.16,	Nos	2				2.00		
						2.00	1150.00	2300.00
Supplying and fixing 50mm GM Gate Vavle (PWD SR 18-19, SI No.673 P.No-XXVI Code No.0164)	Nos	2				2.00		
						2.00	1650.00	3300.00
Supplying and fixing 175mm Borewell cap with clampset As per approved Rate per SERED Letter No 2081/2010-11, Dt.28.7.2010,	Nos	2				2.00	500.00	1000.00
Supplying and fixing 50mm GI Union PWD SR 2018-19, P.No.XXXIX	Nos	20				20.00	223.70	4474.00
Supplying and fixing 50mm GI Elbow PWD SR 2018-19, P-XXXIX	Nos	10	2			20.00	111.80	2236.00
Supplying and delivery at site brand new star / Essen / Lotus / Sun shines / Adharsh / GK Controls best indigenous make combined energy meter cum control panel board unit of size 1200x600x350mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3ph, 50 hz, 380/440 volts, AC supply with spring loaded latch, locking device with a key ribs should be provided inside the door canopy apron and louvers ventilators shall be provided the combined energy meter cum control panel board unit suitable for operation on 3ph, 50 hz, 380/440 volts AC supply shall be consists etc., complete the panel board shall be consist etc., complete the panel board shall be fabricated on single unit in the above componenets panel board for suitable pumpset with star delta staretr out door type 10hp to 15 hp PRED ISSUE RATE	Nos	13				13.00		
						13.00	10000.00	130000.00
Providing and fixing of 50mm G.I pipe 'C' class heavy duty for erection of submersible pumpset galvanised tube 50mm supply and delivery of cause heavy duty as per IS/239/1990 (PRED SR P No.56, No 10.1)	Mtrs	1	923.00			923.00		
						923.00	519.30	479314.00
Supplying and fixing 50mm GI collar Heavy duty PRED SR 2012-13 P-III S-86	Nos	9	15.00			135.00	150.00	20250.00
Erection of combined panel board and meter unit with necessary materials and labour including providing cement concrete foundation and cont door type etc., complete PRED ISSUE RATE	Nos	5				5.00	475.00	2375.00
Supplying of TPST with rewirable porcelain channels in SM closer 15/32 amps P-521, Group-Bi-1(b), BWSSB SR 2013-14.	Nos	5				5.00	1320.00	6600.00
Supplying and fixing 500x500x65mm polished wood board made up of less than 15mm thick plank in front plank one end provided for fixing at other end fixing the same of the valve using through bolts and nuts. PRED ISSUE RATE	Nos	5				5.00	302.50	1513.00

2

48	Supplying and fixing LED Type panel board indicating lamp with required colour suitable for 220 v AC 50Hz 12/24 V DC Group 'B'. P-529, I-35(b), BWSSB SR 2013-14.	Nos	5	3.00				
						15.00	385.00	5775.00
49	Supplying and drawing each PVC insulated 650/100 V grade wire in the conduct (Open or Concealed system of wiring) 7/20 or 7/36 copper wire, P-380, I-20, ii(d), BWSSB SR2012-13.	Nos	2	10.00				
						20.00	27.50	550.00
50	Supplying, fixing and wiring heavy duty low voltage capacitors conforming to I 2834, 3 PHASE 400/440 Volts grade for power factor improvement of rotating machinery capacitor in KVAR - rating Nos 2 KVAR Capacity P-402, I-34(a), BWSSB SR 2012-13.	Group 'A'	Nos	5				
						5.00	385.00	1925.00
51	Supplying and fixing miniature Circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required P-526, I-13 (P. a), BWSSB SR 2013-14.	Nos	5					
						5.00	880.00	4400.00
52	Supplying, fixing, wiring earth electrode for grounding conduits, LC cutouts and other equipments on the meter board using 40mm dia 2.90mm thick GI pipe 2.50m long buried in a pit. The pit should be filled with equal proportion of salt and charcoal 150mm around the pipe to complete depth. the connection from the pipe to the conduct etc., is to be established through GI wire of size as per ISI specifications 7.3.3 IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122mm dia P-552, I-7, BWSSB SR 2013-14.	Nos	30					
						30.00	1650.00	49500.00
53	Supplying and fixing class A (medium duty) GI pipe wall thickness not less than 3.25mm on pole. P-555, I-15, BWSSB SR 2013-14.	Nos	2	10.00				
						20.00	286.00	5720.00
	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 Mtr long buried in a pit, / the pit should be filled with equal proportion of salt and charcoal 150mm around the pipe to complete depth the connections from the pipe to the conduits etc., is to be established through GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12 mmdia bolts, nuts washers and checknuts etc., the pipe shall have 16 through holes of 122mm							
	Cost of UG cable	Nos	2	2.00				
						4.00	1650.00	6600.00
	Labour charges for laying 1.1 KV class UG cable when supplied by agencies in existing trenches GI pipe / stoneware pipe/ on pole as required, P-427, I-11 (a), BWSSB SR 2012-13.							
		Mtrs	2	30.00				
						60.00	5.50	330.00
	Digging of trench of 0.6m deep x 0.5m wide refilling the trench to the required level and consolidating etc., complete P-427, I-12 (a), BWSSB SR2012-13.							
		Mtrs	2	30.00				
						60.00	44.00	2640.00
	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 mm UG cable filled with necessary bitumen / insulating compound complete with terminalas, clamps, bolts, nuts, washers etc., P-428, I-36(b), BWSSB SR 2012-13.							
		Nos	2	30.00				
						60.00	264.00	15840.00

[Handwritten signature]

58	Supplying and fixing of porcelain fuse channel with cut-out on existing / new wooden panel using necessary nuts, bolts and washers etc., BWSSB SR P-394 I-173	Nos	2	6.00		12.00	440.00	5280.00
59	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Asphalt surface road. (Pg. No-269, I.No-37.38) PWD SR 2018-19	Cum	2	100.00	0.60	18.00	475.94	8567.00
60	Earthwork excavation for foundation of buildings water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. Noll KBS 2.1.C/2.9.4/2.18/2.19 (Pg. No-06, I.No-2.4) PWD SR 2018-19	Cum	1	250.00	0.45	67.50	475.94	32126.00
61	KSRB 13.9: Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure of outside diameter raising mains & exposed distribution pipes with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM and testing complete as per specifications. 63MM dia Specification No KBS 13.2.15.2 (Page no:96, I.No.13.73.2 PWD SR 2018-19).	Rmt	1	250.00		250.00	394.32	98580.00
	Basic Rate	372.00						
	Add Area Weightage 6%	22.32						
	Total	394.32						
	Supplying and fixing 50 mm GI pipes 'B' class heavy duty (As PER bwssb Store Issued Rate) Note:- GI Pipe using for Road crossing	Mtrs	1	90.00		90.00	325.00	29250.00
	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m. Including cost of all labour complete as per specification. (Pg. No-7, I No-2 11 PWD SR 2018-19))	Cum				150.00	128.00	19200.00
	Erection of Pumping machineries PRE SR 2012-13 PG 51/10.3.20					10.00	900.00	9000.00
						Sub Total		2489123.0
	Tender Premium Charge 5%							150000.00
	GST Charge 12%							360000.00
	Miscellaneous and Unforeseen Charges							877.00
							TOTAL	3000000.0

(Rupees Thirty Lakhs Only)

Assistant Engineer
Ward-14

Asst. Exe. Engineer
T.Dasarahalli Sub-Division
B.B.M.P.

EXECUTIVE ENGINEER
Dasarahalli Division
Bruhat Bangalore Mahanagara Palike
Bangalore-560005

ನಂ. EE/DD/As/112) ದಿನಾಂಕ : 19.20
17/06/19
ರೂ. Rs. 30.00 Lakhs (Rupees
Thirty Lakhs only)
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಶಾಖಾಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಸಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ನಂ. CE/D2/TS/107) ದಿನಾಂಕ : 02/02/2019
ರೂ. 30.00 Lakhs/- (Rupees
Thirty Lakhs only)
ಈ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.
ತಾಂತ್ರಿಕ ಸಹಾಯಕರು ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಸಿ.ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ಶಾಖಾಪಾಲಕ ಅಭಿಯಂತರರು

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Division, Bangalore-57